



Component	Delivery	
FE	Exhaust fan with EC drive	installed / wired / configured
FS	Supply fan with EC drive	installed / wired / configured
CT*	Motorised damper CT	separately
H	Heating	
	KWin* : Electrical coil "frost protection"	installed / wired / configured
	KWout* : Electrical post-heating coil	separately
	EBA* : Internal Water Heating coil	separately
	3-way valve, Valve actuator	separately
F	Filter	installed
	OUT ePM1 50% (F7) / EXT ePM10 50% (M5)	
C/H*	Heating / Cooling	
	KW* : Electric heating	separately
	EBA+/-* : Change over coil	separately
C*	Cooling	
	EBA-* : Cooling coil	separately
T1	Outdoor temp.	installed / wired / configured
T2	Extract temp.	installed / wired / configured
T3	Exhaust temp.	
T4	Frost protection temp.	installed / wired / configured
T7	Frost protection temp.	separately
T8	Frost protection temp.	separately
CO2* (RH)*	Sensors CO ² , Humidity	separately
CA*	Constant airflow kit	installed / wired / configured
AP*	Pressure switch	separately
Pa*	Pressure sensor	installed / wired / configured

Changes		Name	Date
Name	Date	Draw.:	Beckers
		check.:	Pary
		Norm:	
Subject:	GLOBAL_Fow chart_EN.sp17		GLOBAL PX FW